



c/ Virgilio 22 Bajos Can Pastilla
CP 07610 Palma de Mallorca – Balears
Tel: (34) 971 918 268 – Fax (34) 971 918 269
Móvil: (34) 671 608 268
E-mail jcasas@calacorral.com
Web: www.calacorral.com

Planta de cemento completa con capacidad de producción garantizada

de 750 ton/ día

Instalable en cualquier parte del mundo



La oferta de la planta de cemento que actúa alrededor de un trabajo con 2 líneas A 750 ta/to, por el que los motores y las transmisiones son del año 1981 y las otras partes tales como control y **Ofenmauerung (furnace lining)** etc. son totalmente nuevas.

El trabajo está de tal manera desarrollado que una trituradora y 1 instalación de empaquetado son necesarias.

Este precio contiene: Desmontaje, reacondicionamiento general, **Sandstrahlen (Sand blast)** tan bien como **Lackierung (varnish)** y el cargamento, transporte, reconstrucción, start-up así como movimiento del precio de Engineering.

Precio 25 millones €+ 3% intermediación.

El precio real puede ser determinado solamente si conocemos la localización de la instalación (país/ciudad).

En el precio se incluyen una ayuda de la producción, formación y el entrenamiento de los trabajadores. El trabajo será curado durante 6 meses a partir del start-up por nuestros encargados de trabajo.

Período de la garantía: 12 meses a partir de el principio de la fabricación.

Por otra parte necesitamos antes de la entrega de una LOI + BCL (tipo el carácter de la capacidad del banco)

En el precio no sea incluido: Zivilworks tal como edificios, **Fundamente (Fundamento)**, **Strom-(Conexion) (Power Connection)** und **Wasseranschlüsse (Water Connection)**, etc.

La construcción de la estructura para la primera línea lleva 1 año a partir de la conclusión de un contrato

La segunda estará lista a los 6 meses. Al cabo de un plazo entre 30 y 45 días después de la conclusión de un contrato y de un recibo del pago de el 1.º, se entregarán al cliente los planes para las fundaciones y los edificios. Ésta es solamente una información básica.







One line of two

EQUIPEMENT LIST CEMENT FACTORY

DAY PRODUCTION - 750 TON.

Code	Second hand equipment	New equipment	Electric end electronic Equipment
0			
1		Primary crusher	
2		Mineral extractor	
2/a		Crumbled conveyor	
2/b		Crumbled bucket elevator	
2/c		Crumbled extractor	
2/d		Crumbled conveyor tape	
3	Crumbled balances		
4	Body mineral flour mill (Polysius diam. 2.90 m. length 13.00m - 1982)		
5	Complete motorization(a.b.b-1981)		Complete motorization
6	Redactor(Bonfiglioli-1981)		
7	Transmission shaft(Nuovo pignone-1981)		
8	Body supports (Polysius)		
9	Mineral flour Conveyor tape		Mineral flour Conveyor tape
10	Mineral flour bucket elevator		Mineral flour bucket elevator
11	Body mineral flour separator		Body mineral flour separator
13	Ciclones		
14	Ventilator		Ventilator
15	Bag filter		
16	Mineral flour conveyor screw		Mineral flour conveyor screw
17	Mineral flour conveyor pipe		
18	Hopper		
18/a	Mineral flour conveyor tape		
18/b	heat air generator		heat air generator
19		Mineral flour bucket elevator	
20	Carbon mill body		
21	Complete motorization		Complete motorization
22	Redactor		
23	Transmission shaft		
24	Body support		
25		Mineral flour bucket elevator	
25/a		Mineral flour extractor	
26		Mineral flour conveyor tape	
27	Balances		
28	Granulator water disk		
29	Grate LEPOL/decarbonator		
30	Electrostatic filter(Lepol-1982)		Electrostatic filter
31	clinker conveyor chain		clinker conveyor chain
32	Oven rotary body(Humbolt-diam.2.750 m- long 37.00mt)		
33	Complete motorization (A.B.B. 1981)		Complete motorization
34	Redactor (Bonfiglioli-1981)		
35	Transmission shaft (Nuevo pig none)		
36	Roller equipment(Humbolt)		
37		Carbon burner	
38		C.D.R. burner	
39	Grate / RECUPOL		
40	Conveyor chain / PETERS		Conveyor chain / PETERS
41	Chaine / LUISE		Chaine / LUISE
42	Ventilators (A.B.B.)		Ventilators
42/a		Clinker conveyor tape	
43		Clinker bucket elevator	
44		Clinker extractor	
44/a		Clinker conveyor tape	
45	Balances		
46	Clinker conveyor tape		Clinker conveyor tape
47	Body cement mill (Polysius - diam.2.900 m. Long .12.00 m 1982)		
48	Complete motorization (A.B.B.)		Complete motorization
49	Reductor (Bonfiglioli)		
50	Transmission shaft (Nuovo pignone)		
51	Body supports(Polisius)		
51/a	Cement conveyor belt		Cement conveyor belt
52	Cement bucket elevator		Cement bucket elevator
53	Body cement separator		
54	Cyclones		
55	Ventilator(A.B.B.)		Ventilator
56	Bag filter		
57	Cement conveyor screw		Cement conveyor screw
58	Cement conveyor pipe		
58	Hopper		
59	Cement Conveyor pipe		
60	Bag filter		
61	Cement filters		
62	Cement conveyor		Cement conveyor
63		Cement bucket elevator	
64		Cement extractor	
65		Pneumatic cement conveyor	
66		Weigh automatic system	
67		Palletising automatic system	
68		Coiling automatic system	
69	Iron spheres contaier		
70	Spare Parts		